

# Ironwood at Hammonds Ferry

North Augusta, South Carolina

Compacted aggregate piers (AMPier) were installed to support two new buildings. About 6 feet of soil was reportedly undercut to remove kilns from an old brick factory. Aggregate piers were installed to improve the brick laden fill that will be put back in place once the kilns are removed. Aggregate piers will provide 2,500 psf bearing capacity for the spread foundations.



GC: Landsouth Construction, LLC  
Geotechnical Consultant: S&ME  
Geotechnical Contractor: WEC